

(1) PLY ALSAN FULLY REINFORCED LIQUID MEMBRANE PATCH, ROUND ALL FLEECE CORNERS.

EXISTING IN-PLACE ALSAN FULLY REINFORCED LIQUID MEMBRANE (SEE NOTE #2).


AREA OF DAMAGED MEMBRANE REMOVED

4" MIN.

4" MIN.

NOTES:

1. DETAIL TO BE USED IN CONJUNCTION WITH SOPREMA GENERAL REQUIREMENTS, APPLICATION METHODS AND APPROVED DETAILS.
2. A FULLY REINFORCED LIQUID MEMBRANE SYSTEM IS DEFINED AS AN ASSEMBLY CONSISTING OF TWO LIQUID RESIN APPLICATIONS & FABRIC REINFORCEMENT INSTALLED BETWEEN THE RESIN LAYERS. REFER TO DETAIL A-1 FOR ADDITIONAL INFORMATION.

		310 QUADRAL DRIVE WADSWORTH, OHIO 44281 (330) 334-0066					
		TITLE TIE-IN REPAIR					
SCALE	NONE	DWN	PBF	CHK	BS	APPROVAL DATE	8/11/09
DRAWING NUMBER	M-6					REV	0

\*\* USAGE OF THIS DRAWING IS GOVERNED BY THE TERMS OF SERVICE FOR SOPREMA DETAIL. PLEASE CONSULT THESE TERMS OF SERVICE PRIOR TO UTILIZING THIS DRAWING.