


NOTES: (SEE DETAIL SFMA-009)

1. DETAIL TO BE USED IN CONJUNCTION WITH SOPREMA GENERAL REQUIREMENTS AND APPROVED DETAILS. FOR BUILDINGS; LESS THAN 60' IN HEIGHT IN GROUND ROUGHNESS CATEGORIES 'B' AND 'C' WITH MAX. 90 MPH WIND ZONE WITH FMG APPROVED 22 GA STEEL OR CONCRETE DECKS. FOR FASTENER SPACING ON OTHER DECK TYPES CONTACT SOPREMA CORPORATE TECHNICAL DEPARTMENT.
2. FMG PERIMETER DEFINITION: $X=4/10$ OF BUILDING HEIGHT OR $1/10$ THE BUILDING WIDTH, WHICHEVER IS THE LESSER DIMENSION. SOPREMA REQUIRES A MINIMUM OF 3 PERIMETER ROLLS. THE NUMBER OF PERIMETER ROLLS AND FASTENER DENSITIES MAY INCREASE WHEN WIND WARRANTY RIDERS ARE APPROVED.
3. PERIMETER FASTENER ROW SPACING: 60% OF FIELD FASTENER ROW WIDTH OR 20" (51cm).
CORNER FASTENER ROW SPACING: 40% OF FIELD FASTENER ROW WIDTH OR 13" (33cm).

		310 QUADRAL DRIVE	
		WADSWORTH, OHIO 44281	
		(330) 334-0066	
TITLE Soprafix FMG 1-90 Perimeter & Corner 2			
SCALE	DWN	CHK	APPROVAL DATE
NONE	DMT	BS	11/17/06
DRAWING NUMBER			REV
SFMA-011			0

** USAGE OF THIS DRAWING IS GOVERNED BY THE TERMS OF SERVICE FOR SOPREMA DETAIL. PLEASE CONSULT THESE TERMS OF SERVICE PRIOR TO UTILIZING THIS DRAWING.